

- | | | | |
|-------------|---|-----------|------------------|
| 1. 성적서 번호 : | CMT2016 - 0117 | 5. 접수일자 : | 2015 년 12 월 14 일 |
| 2. 의뢰인 | 업체명 : (주)아워브레인 | 6. 발급일자 : | 2016 년 01 월 08 일 |
| | 주 소 : 서울특별시 강남구 역삼로 542 | | |
| | 성 명 : 인 승 철 | | |
| 3. 성과이용목적 : | 보고서작성용 | | |
| 4. 시 료 명 : | 콘크리트 분말(2015년(하반기) 정밀안전진단 및 정밀점검용역(1구간) : 청도천1교-상,하행) | | |

시험 결과

연 번	구 분		시험 · 검사종목	단 위	시험 · 검사방법	시험 · 검사결과
1	상행	S1	전 염화물	%	KS F 2713 -'02	0 -20mm : 0.0905 20-40mm : 0.0233
			환산 염화물함량	kg/m³		0 -20mm : 2.049 20-40mm : 0.528
2		A1 (우수접촉부)	전 염화물	%	KS F 2713 -'02	0 -20mm : 0.0230 20-40mm : 0.0172
			환산 염화물함량	kg/m³		0 -20mm : 0.521 20-40mm : 0.389
3		A1 (건전)	전 염화물	%	KS F 2713 -'02	0 -20mm : 0.0220 20-40mm : 0.0177
			환산 염화물함량	kg/m³		0 -20mm : 0.497 20-40mm : 0.400

※ 환산염화물 산출시 콘크리트의 단위중량은 2,263kg/m³ 적용 : KS F 2714-'02

- 계 속 -

담당자 : 김 호 진
Tel : 031-646-0804



기술책임자 : 신 도 철
Tel : 031-646-0801



- ※비 고 : 1. 이 시험성적서는 당초 의뢰자가 제출한 시료 및 시료명으로 시험한 결과로서 전체 제품에 대한 품질을 보증 하지는 않습니다.
2. 이 성적서는 홍보, 선전, 광고 및 소송용으로 사용될 수 없으며, 용도 이외의 사용을 금합니다.
3. 이 성적서의 원본 진위확인을 원하시면은 시험담당자의 열람요청을 통해서 확인해 드립니다.

한국에스지에스(주) 건설시험연구원

주 소 : 경기도 평택시 서탄면 수월암5길 66 전화번호 (031)669-0600

유의사항 : 기술책임자의 성명과 서명이 없는 경우에는 결과에 대한 보증을 할 수 없습니다.



페이지 1 / 2

This document is issued by the Company under its General Conditions of Service accessible at <http://www.sgs.com/en/Terms-and-Conditions.aspx>. Attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein. Any holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents. Any unauthorized alteration, forgery or falsification of the content or appearance of this document is unlawful and offenders may be prosecuted to the fullest extent of the law.

KQP-2510-001-F07 (06)



연 번	구 분		시험 · 검사종목	단 위	시험 · 검사방법	시험 · 검사결과
4	하행	S1	전 염화물	%	KS F 2713 -'02	0 -20mm : 0.1011 20-40mm : 0.0378
			환산 염화물함량	kg/m³		0 -20mm : 2.289 20-40mm : 0.855
5		A1 (우수접촉부)	전 염화물	%	KS F 2713 -'02	0 -20mm : 0.0230 20-40mm : 0.0173
			환산 염화물함량	kg/m³		0 -20mm : 0.521 20-40mm : 0.390
6		A1 (건전)	전 염화물	%	KS F 2713 -'02	0 -20mm : 0.0264 20-40mm : 0.0198
			환산 염화물함량	kg/m³		0 -20mm : 0.597 20-40mm : 0.448

- 끝 -