

RC-RADAR		차령터널(천안) 철근탐사 자료					
PROJECT TITLE		시설물 정밀안전진단 용역 [2구역]					
Company		 (주) 한국구조물안전연구원  (주) 한 맥 기 술	Client		 (주)천안논산고속도로		
시험 결과							
No	위치	철근방향	실측 배근간격 (mm)	설계 배근간격 (mm)	실측 피복두께 (mm)	설계 피복두께 (mm)	비고
1	S2 측벽부	주철근	140~160	150	81~86	34.0	양호
		배력철근	210	200	95	66.0	양호
2	S3 천단부	주철근	135~155	150	74~79	34.0	양호
		배력철근	195~205	200	112~119	66.0	양호
3	S82 천단부	주철근	115~135	125	36~44	40.5	양호
		배력철근	135~150	150	69~77	59.5	양호
4	S144 천단부	수직철근	105~120	125	52~67	40.5	양호
		수평철근	125~145	150	107~117	59.5	양호
5	S205 천단부	수직철근	105~125	125	49	40.5	양호
		수평철근	140~160	150	65~72	59.5	양호
6	S266 천단부	수직철근	150~160	150	60~62	34.0	양호
		수평철근	195~205	200	103~105	66.0	양호
7	S268 측벽부	수직철근	135~155	150	49~60	34.0	양호
		수평철근	205	200	67~69	66.0	양호





